



Hunt Regional Healthcare

Greenville, TX

Size

10,000 sq ft

Construction

UBC Type V-N

Facility Use

Medical Professional building

Description

Five office suites
Distinctive offset design
Carrara exterior finish
Brick wainscot
Wood frame
Membrane roof

Completion

180 days

Accelerated
Building System



Ramtech designed and constructed the building modules utilizing its Accelerated Building System and provided full construction services including the development of a multi-acre site and installation of the modules comprising this 10,000 square foot medical office building in Greenville, Texas.

The facility and site was designed as the anchor building in a planned medical office park. This fast-track project required the use of modular construction to meet a critical need for medical office space.



The project features offset modules with "Carrara" elastomeric finish and brick wainscot capped with waterfall moldings. The building contains five separate office suites, each with waiting areas, exam and rooms, offices and nurse's station. The smaller suites are approximately 1,200 square feet while the largest is over 2,400 square feet.



RAMTECH
Building Systems
800-568-9376
ramtechmedical.com