

## Project Size

23,808 sf  
8 buildings across  
7 campuses

## Construction

Type V-b

## Contract Type

BuyBoard

## Facility Use

Elementary, middle, &  
high school classrooms  
and admin space

## Description

Wall-hung HVAC units  
HardiePanel exterior

## Completion

60 days

Traditional  
Modular  
Construction



The Plano I.S.D. has been a large user of Ramtech's four-classroom buildings, both to meet increased enrollments for all grade levels and as special use classroom space at multiple locations. Some of the facilities were also used to meet temporary space requirements while renovations to the districts existing structures were taking place. Purchased through the Texas Buyboard and built using traditional modular construction, all the facilities employ four wall-mounted HVAC units to provide for individual climate control in each classroom. The interiors feature vinyl composition gypsum wall coverings and durable high traffic carpet flooring. To meet the City's masonry requirements, the exteriors utilize a HardiePanel fiber cement siding with an elastomeric paint finish.